


Continuous preparation of aldehydes

The present invention relates to a process for the continuous preparation of aldehydes having from 5 to 21 carbon atoms by isomerizing hydroformylation in the homogeneous phase of olefin compositions having from 4 to 20 carbon atoms and comprising α -olefins and olefins having internal double bonds by means of synthesis gas in the presence of a homogeneous rhodium catalyst complexed with an oxygen- and/or nitrogen-containing organophosphorus ligand and free ligand at elevated temperature and elevated pressure in a multistage reaction system comprising at least two reaction zones.

In 1990, the annual world production of products from the hydroformylation of olefins, also known as the oxo process, was estimated to be about 7 million metric tons. Although mostly homogeneous catalysts based on cobalt were employed at the beginning of the industrial application of the oxo process, homogeneous hydroformylation catalysts based on rhodium have been increasingly used in industry since the 1970s because they make it possible to work economically at lower temperatures and, in particular, at a lower pressure than in the case of cobalt catalysts and achieve a high n/i selectivity in the hydroformylation of olefins having a terminal double bond (α -olefins). For this reason, the low-pressure hydroformylation using generally triphenylphosphine-modified rhodium complexes has virtually completely displaced the high-pressure hydroformylation using cobalt carbonyl catalysts in the industrial preparation of C₃- and C₄-aldehydes from ethene and propene, respectively. Nevertheless, the high-pressure hydroformylation using cobalt carbonyl catalysts is still of considerable industrial importance even today, in particular in the hydroformylation of long-chain olefins having internal double bonds. Such olefins are available in large quantities, for example as raffinate II (from the C₄ cut of a steam cracker after removal or selective hydrogenation of dienes, such as 1,3-butadiene and removal of isobutene-based C₄ mixture comprising butene-1 and butene-2) or from olefin dimerization processes and trimerization processes or from olefin metathesis plants and Fischer-Tropsch plants and their oxo products serve as starting materials for the preparation of other industrial products such as plasticizers or surfactant alcohols. Owing to the way in which they are produced, these olefins are generally in the form of an isomer mixture of α -olefin concerned and the corresponding structural isomers having an internal double bond and are used in this form as starting material for the oxo process. For the purposes of the present invention "internal" olefins are accordingly olefins whose double bond is, unlike α -olefins, not terminal but located in the interior of the olefin molecule.

The reason why cobalt catalysts are preferred for the hydroformylation of such relatively long-chain olefin mixtures and also for the hydroformylation of individual olefinic compounds having internal double bonds despite the higher temperatures and higher pressures required when using cobalt catalysts may be found in the different

- 5 catalytic behavior of the catalyst metals cobalt and rhodium. In the hydroformylation of α -olefins, it is possible, depending on the site of addition of the CO molecule to the double bond in accordance with the equation (1)



10

for linear aldehydes A, known as n-aldehydes, or branched aldehydes B, also referred to as iso-aldehydes, to be formed. In general, a higher proportion of n-aldehydes in the hydroformylation product, expressed by the n/i ratio, i.e. the molar ratio of n-aldehydes to iso-aldehydes in the reaction product, is desired. Although the rhodium-

- 15 triphenylphosphine catalyst system leads to high n selectivities in the hydroformylation of short-chain α -olefins, this catalyst system has disadvantages in the hydroformylation of the abovementioned olefin mixtures or olefins having internal double bonds. Firstly, the rhodium-triphenylphosphine catalyst system displays only a very low hydroformylation activity toward internal double bonds, with the result that such
- 20 "internal" olefins either do not react at all or react to an economically acceptable extent only when using uneconomically long reaction times, and, secondly, this disadvantage is made worse by the fact that this catalyst system also isomerizes terminal double bonds to internal double bonds to a significant extent under the conditions of the hydroformylation reaction, so that when the rhodium-triphenylphosphine catalyst
- 25 system is used in the hydroformylation of such industrial olefin isomer mixtures or internal olefins, only unsatisfactory olefin conversions and unsatisfactory degrees of utilization of the internal olefins are achieved.

- To be able to utilize the inherent advantages of the low-pressure hydroformylation
- 30 using rhodium catalysts in the hydroformylation of relatively long-chain olefin mixtures of α -olefins and internal olefins and the hydroformylation of internal olefins, efforts have long been made to develop rhodium-catalyzed "isomerizing" hydroformylation processes, viz. processes in which the proportion of n-aldehydes in the reaction product from the hydroformylation of internal olefins or mixtures of α -olefins and internal olefins is higher than would have been expected from the proportions of terminal and internal double bonds in the starting olefin and the double bond isomerization effected by the rhodium-triphenylphosphine catalyst system. Research

aimed at achieving this goal has hitherto focused on modification of the properties of the rhodium catalyst by means of suitable ligands and/or process engineering measures. However, there is still a need for considerable improvement in order to achieve economically successful use in isomerizing hydroformylation in industrial
5 practice.

As rhodium catalyst systems suitable for isomerizing hydroformylation, mention may be made by way of example of merely the rhodium complexes with organophosphite ligands described in US-A 3 527 809, the rhodium complexes with chelating
10 organophosphite ligands described in US-A 4,668,651 and the rhodium complexes with organophosphoramidite ligands and organophosphite or organophosphonite ligands described in WO 01/58589 and WO 02/83695.

Since the n/i selectivity in the hydroformylation of olefins is influenced by many
15 parameters, the use of such catalysts for isomerizing hydroformylation has to be accompanied by process engineering measures and measures involving the reaction conditions in order to achieve economically satisfactory results. One parameter which has already been identified by d' Oro et al, LA CHIMICA ET L'INDUSTRIA 62, 572 (1980) as having a significant influence on the n/i selectivity in hydroformylations using
20 the rhodium-triphenylphosphine catalyst system is the CO partial pressure in the hydroformylation reactor. It was in this case found that although reducing the CO partial pressure leads to an increase in the n selectivity, such a reduction in the CO partial pressure results in an undesirably large increase in the hydrogenation rate of the olefins used, and thus a high level of paraffin formation.

25 In US-A 4,885,401, it is stated that a reduction in the CO partial pressure in the hydroformylation reactor when using rhodium-chelating phosphite catalyst systems leads to an increase in the reaction rate and that the CO/H₂ ratio should preferably be from 1:1 to 1:10.

30 Example 12 of US-A 4,885,401, which concerns the hydroformylation of 2-butene, indicates that although the reaction rate is increased when the CO/H₂ ratio is reduced, the n/i ratio of the aldehydes formed decreases.

35 US-A 4,885,401 mentions in general terms the possibility of hydroformylating mixtures of α -olefins and internal olefins in a series of different reactors and, if desired, setting the optimum reaction conditions independently in the individual reactors, but specific teachings on the way in which this should be done and the direction of the optimization measures are not provided.

US-A 4,599,206 contains examples relating to the hydroformylation of butene-1/butene-2 mixtures using a rhodium organomonophosphite ligand catalyst in two successive reactors which are operated at different CO/H₂ molar ratios. However, the greatly varying reaction conditions of these examples make it impossible to discern

- 5 from the individual results any generalizable teaching as to how to conduct an isomerizing hydroformylation to achieve high n/i ratios of the product aldehydes coupled with a high butene conversion.

EP-A 188 426 describes a process for the hydroformylation of olefins in which the

- 10 olefin-containing offgas from a first reactor system is fed into a second reactor system which is decoupled from the first reactor system to complete the hydroformylation. It is possible for the reaction conditions employed in the second decoupled reactor system to be different from those employed in the first, in particular different catalyst systems can be employed there. The use of these decoupled reactor systems is said to achieve
15 more efficient and more complete utilization of the olefins fed in. EP-A 188 426 does not refer to hydroformylation under isomerizing conditions and the examples in this document are accordingly restricted to the use of the rhodium-triphenylphosphine catalyst system for the hydroformylation of propene. Furthermore, there are no teachings as to how the n/i ratio can be increased when using internal olefins as
20 starting material.

WO 97/20801 (\cong US-A 5,744,650) specifically addresses the relationship between hydroformylation rate and carbon monoxide partial pressure in hydroformylations using rhodium-organopolyphosphite catalysts, the prevention of or reduction in the

- 25 deactivation of the rhodium-organopolyphosphite catalyst, the prevention of and/or reduction in periodic fluctuations in the carbon monoxide partial pressure, the hydrogen partial pressure, the total reaction pressure, the hydroformylation rate and/or the temperature during the hydroformylation process and proposes, as a solution to these problems, that the hydroformylation process be carried out at a carbon monoxide
30 partial pressure which is such that the hydroformylation rate increases when the carbon monoxide partial pressure decreases and the hydroformylation rate decreases when the carbon monoxide partial pressure increases and that one or more of the following conditions are met:

- 35 a) the use of a temperature which is such that the temperature difference between the temperature of the reaction product liquid and the inlet temperature of the coolant is less than 25°C,
b) a carbon monoxide conversion of less than 90%,
c) a hydrogen conversion of more than 65% and
40 d) a conversion of the olefinically unsaturated compound of more than 50%.

As regards the effects of the carbon monoxide partial pressure on the n/i selectivity, WO 97/20801 merely observes that working in a range in which the hydroformylation has a negative order of reaction in respect of the carbon monoxide partial pressure, i.e.

- 5 at a relatively high carbon monoxide partial pressure, leads to a high isomer ratio.

The continuation-in-part patent US-A 5 874 639 extends the subject-matter of US-A 5,744,650 to the use of catalysts comprising organopolyphosphorus-metal complexes.

10

US-A 5 728 893 relates to the use of a specifically constructed multistage reactor for hydroformylations, with the purpose of achieving reaction conditions in which a change in the n product selectivity of 0.2% of n product per 1 pound per square inch of CO partial pressure ($\pm 2.9\%$ per bar of CO partial pressure) is not exceeded. The only

15

examples in this patent concern the conventional hydroformylation of ethylene and propene using the rhodium-triphenylphosphine catalyst system and using an excess of hydrogen from the beginning. According to the data from the examples, an increase in the CO partial pressure leads to a reduction in the hydroformylation rate. No information is given about the n/i ratio of the butyraldehydes produced in the

20

hydroformylation of propene in Example 2.

According to JP-A 143 572 (2000), the hydroformylation should be carried out under conditions under which the carbon monoxide partial pressure in the reactor has virtually no effect on the reaction rate.

25

Reinius et al (J. Mol. Cat. A: Chemical 158, 499 (2000)) studied the hydroformylation of methyl methacrylate using a rhodium-methyl(thienyl)diphenylphosphine complex as catalyst and came to the conclusion that increasing the H₂ partial pressure in the synthesis gas does not alter the n/i selectivity of the hydroformylation reaction, in contrast to the situation when a triphenylphosphine-rhodium complex is used as catalyst.

In Catalysis Today 74, 111 (2002), Yang et al. describe the influence of the H₂ and CO partial pressure on the catalytic activity of the rhodium-tris(sodium m-

sulfonatophenyl)phosphine complex in the hydroformylation of propene. They found

35

that in the case of this catalyst system the hydroformylation rate increases with increasing H₂ partial pressure and decreases with increasing CO partial pressure.

EP-A 423 769 relates to the use of a combination of two different reactors connected to form a reactor cascade in the multistage hydroformylation of olefins. According to the

40

examples in this patent application, the hydroformylation of propene in the presence of

the conventional rhodium-triphenylphosphine catalyst system is carried out using synthesis gas mixtures in which the proportion of hydrogen exceeds the proportion of carbon monoxide both in the first and second reaction stages. EP-B 423 769 gives no information on isomerizing hydroformylation.

5

EP-A 1 008 580 likewise relates to the use of a reactor cascade comprising at least two reactors which are divided into pressure sections for hydroformylation, where the relationship between the H₂ and CO partial pressures in the first (m-1)-th pressure section and the corresponding partial pressures in a downstream second (m-th)

10 pressure section is in accordance with at least one of the following inequalities,

$$p_{CO}(m-1) < p_{CO}(m)$$

$$p_{H_2}(m-1) < p_{H_2}(m)$$

$$p_{CO}(m-1) + p_{H_2}(m-1) < p_{CO}(m) + p_{H_2}(m)$$

15

where p_{CO} and p_{H₂} are the CO and H₂ partial pressures in the respective pressure section or reaction stage. This mode of operation is said to increase the hydroformylation rate and also improve the n/i selectivity. According to the examples in EP-A 1 008 580, this is achieved in the hydroformylation of an octene mixture using

20 synthesis gas having a CO/H₂ molar ratio of 1:1 by setting a pressure of 50 kg/cm² in the first reaction stage and a pressure of 170 kg/cm² in the second reaction stage. The hydroformylation catalyst used here is uncomplexed hydridorhodium carbonyl which is generated in situ in the reactor. Although it is said in the description of EP-A 1 008 580 that this process is also suitable for hydroformylations using cobalt and rhodium

25 catalysts complexed with various phosphite or phosphine ligands, specific examples and information on the effects of this process on the n/i ratio of the aldehydes produced when using catalysts which behave differently from uncomplexed rhodium are lacking.

Carrying out a second reaction stage at a CO partial pressure which is higher than the
30 CO partial pressure in the first reaction stage is also disclosed by US-A 4,716,250 (Example 9) for the hydroformylation of 1-octene by means of a rhodium catalyst complexed with a monosulfonated phosphine. As regards the CO/H₂ ratio in the individual reaction stages, an excess of hydrogen is present in both the first and second reaction stages. However, the best result in respect of the n/i ratio of the
35 nonanals formed (n/i ratio = 12.3) is achieved in a variant different from Example 9 when using an approximately equal CO partial pressure in the first and second stages and when using a high H₂/CO molar ratio both in the first and second reaction stages.

WO 02/68371 relates to an isomerizing hydroformylation process in a reactor cascade
40 using a conventional rhodium-triphenylphosphine catalyst in the first reaction stage and

a rhodium catalyst modified with a chelating diphosphine having a xanthene backbone in the second reaction stage. When a synthesis gas having a CO/H₂ ratio of 1:1 is used, the second reaction stage in this document is, according to the examples, also carried out at a pressure higher than that in the first stage, corresponding to an

- 5 increase of the CO and H₂ partial pressures over the partial pressures in the first stage. However, the use of different catalyst systems is complicated, which considerably increases the costs of this process.

It is an object of the present invention to find a process for the hydroformylation of

- 10 mixtures of internal olefins and α -olefins which, despite the opposite dependences of the reaction rate and the n selectivity on the CO partial pressure as indicated by the prior art, makes it possible to prepared aldehydes economically from such olefin mixtures with a high n selectivity and at a high space-time yield. For this purpose the isomerization of internal double bonds to terminal double bonds in the internal olefins
15 present in the olefin mixture should be promoted and at the same time the double bond izomerization of α -olefins to internal olefins should be suppressed, since the latter reduces the total space-time yield of the process because internal olefins are basically less reactive than α -olefins.

- 20 We have found that this object is achieved by a process for the continuous preparation of aldehydes having from 5 to 21 carbon atoms by isomerizing hydroformylation in the homogeneous phase of olefin compositions having from 4 to 20 carbon atoms and comprising α -olefins and olefins having internal double bonds by means of synthesis gas in the presence of a homogeneous rhodium catalyst complexed with an oxygen-
25 and/or nitrogen-containing organophosphorus ligand and free ligand at elevated temperature and elevated pressure in a multistage reaction system comprising at least two reaction zones, wherein the olefin composition is firstly reacted with synthesis gas having a CO/H₂ molar ratio of from 4:1 to 1:2 at a total pressure of from 10 to 40 bar in a group of one or more first reaction zones to a conversion of the α -olefins of from 40 to 95% and the hydroformylation mixture from this group of one or more first reaction zones is reacted with synthesis gas having a CO/H₂ molar ratio of from 1:4 to 1:1000 at a total pressure of from 5 to 30 bar in a group of one or more downstream reaction zones, where the total pressure in the one or more downstream reaction zones is in each case at least from 1 to (T₁-T_f) bar lower than in the preceding reaction zone,
30 where T₁ is the total pressure in the preceding reaction zone and T_f is the total pressure in the reaction zone downstream of the one or more first reaction zones, with the proviso that the difference T₁-T_f is greater than 1 bar, and the CO partial pressure in the one or more downstream reaction zones is in each case lower than in the preceding reaction zone.

The process of the present invention is based on a number of research results concerning isomerizing hydroformylation. Thus, it has been found, inter alia, that

- a) in the continuous hydroformylation of raffinate II in two reactors connected in series under otherwise identical conditions in both reactors, a decrease in the CO partial pressure, achieved either by reducing the synthesis gas pressure at a constant CO/H₂ molar ratio or by reducing the CO/H₂ molar ratio at a constant total pressure, results in an increase in the aldehyde yield and the proportion of n-valeraldehyde in the hydroformylation product mixture;
 - b) in the batchwise hydroformylation of 2-butene, a reduction in the CO partial pressure leads to an increase in the aldehyde yield and the proportion of n-valeraldehyde; and
 - c) in the batchwise hydroformylation of 1-butene, a reduction in the CO partial pressure leads to an increase in the undesirable isomerization of 1-butene to 2-butene and both the space-time yield of aldehyde formation and the n/i ratio of the valeraldehydes formed decrease as a consequence.
- As a result of use of the measures according to the present invention and setting the process parameters according to the present invention, the α -olefin present in the olefin composition is, according to the present invention, mostly converted, i.e. to a conversion of from 40 to 95%, preferably from 70 to 95%, to the corresponding n-aldehyde in a group of one or more first reaction zones, without isomerization of the terminal double bond to internal double bonds occurring to a substantial extent, so that, in greatly simplified terms, the olefins having internal double bonds in the olefin composition are hydroformylated in a group of one or more downstream reaction zones under hydroformylation conditions which are optimal for the isomerization of internal double bonds to terminal double bonds without this leading to significant isomerization of the α -olefin originally present in the olefin composition, so that an aldehyde product having a high n/i ratio is finally obtained in a high space-time yield from the olefin composition. The extent of undesirable isomerization of the α -olefins to internal olefins in the group of one or more first reaction zones under the hydroformylation conditions should be kept as small as possible and be not more than 80%, preferably less than 50% and particularly preferably less than 30%.

The sought-after conversion of generally from 50 to 99% of the α -olefins present in the olefin composition can thus be brought about in a single first reaction zone or in a plurality of first reaction zones. For the purposes of the present invention, the expression "group of one or more first reaction zones" will be used to refer to this single

first reaction zone or a plurality of first reaction zones. The same applies to the single reaction zone or plurality of reaction zones downstream of the group of one or more first reaction zones. In this "group of one or more downstream reaction zones", the main objective is the isomerizing hydroformylation of the internal olefins in the olefin
5 composition to be hydroformylated.

The process of the present invention thus differs from the prior art relating to the stepwise hydroformylation of olefin mixtures comprising α -olefins and internal olefins by means of reaction zones which are cascaded, i.e. gradated, in respect of the pressure
10 and the CO/H₂ ratio (e.g. US-A 4 716 250; EP-A 1 008 580), in that both the CO partial pressure and the total pressure are lower in the group of one or more downstream reaction zones than in the group of one or more first reaction zones, with the group of one or more first reaction zones generally being operated at a relatively high CO/H₂ molar ratio and a significantly higher total pressure than the group of one or more
15 downstream reaction zones.

In the process of the present invention, the hydroformylation of olefin compositions having terminal and internal double bonds is carried out in a multistage reaction system which is cascaded in respect of the process parameters total pressure, CO/H₂ molar
20 ratio and CO partial pressure and comprises a plurality of reaction zones, e.g. from 2 to 10, preferably from 2 to 4 and particularly preferably two (2) reaction zones, connected in series, where the individual reaction zones differ from one another in terms of the different total pressure, the CO partial pressure and, if desired, the CO/H₂ molar ratio prevailing therein. Thus, the individual reaction zones can be present in the individual
25 reactors connected in series in a reactor cascade, or a single reaction zone can also encompass a plurality of reactors which are connected in series or in parallel and which meet the criteria according to the present invention for an individual reaction zone, essentially the same total pressure and CO partial pressure. Conversely, a single hydroformylation reactor can be segmented by means of suitable internals into a
30 plurality of reaction compartments in which the reaction conditions can be set independently so that one or more of these reaction compartments form a reaction zone and one or more of the downstream reaction compartments of the reactor form, depending on the setting of the process parameters in the individual compartments, a second reaction zone or a plurality of downstream reaction zones. Thus, if a
35 downstream compartment of the reactor is operated at a total pressure which is at least 1 bar lower and the CO partial pressure is lower, if desired at a lower CO/H₂ molar ratio, than in the preceding compartment, this downstream compartment forms a new reaction zone compared to the preceding compartment. Analogous considerations apply to the reaction conditions in individual reactors connected in series.

- As reactors for the process of the present invention, it is in principle possible to use all types of reactors which are suitable for hydroformylation reactions, for example stirred reactors, bubble column reactors as described, for example, in US-A 4 778 929, circulation reactors as described, for example, in EP-A 1 114 017, tube reactors, in the 5 case of which the individual reactors of a series can have different mixing characteristics, as described, for example, in EP-A 423 769, and also compartmentalized reactors as described, for example, in EP-A 1 231 198 or in US-A 5 728 893.
- 10 If a reaction zone encompasses a plurality of reactors, it is possible to use identical or different reactor types in this reaction zone, and it is likewise possible to use identical or different reactor types from reaction zone to reaction zone. Preference is given to using the same reactor types in the individual reaction zones, e.g. circulation reactors or stirred vessels.
- 15 The process of the present invention is generally carried out at a total pressure of generally from 10 to 40 bar, preferably from 10 to 30 bar and particularly preferably from 10 to 25 bar, in the group of one or more first reaction zones and at a total pressure of generally from 5 to 30 bar, preferably from 5 to 20 bar and particularly 20 preferably from 9 to 20 bar, in the group of one or more reaction zones downstream of the group of one or more first reaction zones. The total pressure in the individual reaction zones is the sum of the partial pressures of the reaction gases carbon monoxide (CO) and hydrogen (H₂), the partial pressures of the individual olefins in the olefin composition to be hydroformylated and the aldehydes produced during the 25 hydroformylation and the partial pressures of further components present in the reaction mixture, e.g. saturated hydrocarbons, inert gases such as nitrogen, auxiliaries such as solvents or free ligand, any stabilizers, e.g. tertiary amines or azines, added to the reaction mixture to stabilize the ligands used against degradation reactions and any impurities present in traces in the starting materials, e.g. carbon dioxide, and by- 30 products formed during the hydroformylation. In general, the total pressure in the individual reaction zones is set via the introduction of the reaction gases CO and H₂ and/or via the removal of volatile components by depressurization of the reaction mixture at the respective reaction temperature.
- 35 According to the present invention, the total pressure in the individual reaction zones is set so that the total pressure in a downstream reaction zone is at least from 1 to (T₁ – T_f) bar lower than in the preceding reaction zone, where T₁ is the total pressure in the preceding reaction zone R_m which can in turn be preceded by one or more reaction zones, e.g. R₁, R_k, etc., and T_f is the total pressure in the reaction zone R_n downstream 40 of this reaction zone, where the reaction zone R_n can in turn be followed by further

reaction zones (R_o , R_p , etc.) in which the total pressure obeys the same relationship as that between the reaction zones R_m and R_n . Here, the proviso that the difference $T_1 - T_f$ is greater than 1 bar applies. In general, the total pressure in the downstream reaction zone R_n is from 1 to 25 bar lower, preferably from 1 to 15 bar lower and particularly preferably from 1 to 10 bar lower, than in the preceding reaction zone. The reference point for the total pressure in the individual reaction zones is in each case the total pressure in the reactor – or if a plurality of reactors together form a reaction zone, the total pressure in the last reactor of the preceding reaction zone and in the reactor – or if a plurality of reactors together form a reaction zone; the total pressure in the first reactor of the downstream reaction zone. Corresponding considerations apply to compartmentalized reactors in which one or more individual reaction compartments form a reaction zone. In the case of tube reactors, the total pressure at the outlet of a first tube reactor and the total pressure at the inlet into a downstream tube reactor or other reactors forms the reference point for determining the individual reaction zones. If the total pressure difference between two or more reactors or reaction compartments connected in series is less than 1 bar, these together form a reaction zone.

The reaction temperature in the individual reaction zones is generally from 50 to 200°C, preferably from 50 to 150°C and particularly preferably to 70 to 130°C.

The CO/H₂ molar ratio of the synthesis gas in the group of one or more first reaction zones in the process of the present invention is generally from 4:1 to 1:2, preferably from 4:1 to 2:3 and particularly preferably from 3:2 to 2:3 (CO:H₂), and that in the group of one or more reaction zones downstream of the group of one or more first reaction zones is generally from 1:4 to 1:1000, preferably from 1:4 to 1:100 and particularly preferably from 1:9 to 1:100 (CO/H₂), where the CO partial pressure in a downstream reaction zone is set to a value lower than the CO partial pressure prevailing in the reaction zone immediately preceding this reaction zone. In general, the CO partial pressure in the reaction zone downstream of the one or more first reaction zones is set to a value which is from 1 to 20 bar lower, preferably from 1 to 10 bar lower and particularly preferably from 2 to 7 bar lower, than the CO partial pressure prevailing in the immediately preceding reaction zone.

As regards the reference points for determining the CO partial pressure in the individual reaction zones, what has been said above for determining the total pressure in the individual reaction zones applies analogously.

The optimum total pressure, the optimum CO/H₂ molar ratio and also the optimum CO partial pressure in the individual reaction zones of the process of the present invention depends on the type and composition of the olefin composition to be hydroformylated,

- for example the chain length of the olefins to be hydroformylated, the proportions of terminal and internal double bonds, the position of the internal double bonds and possibly the degree of branching of the olefins. Accordingly, these process parameters are, according to the present invention, advantageously optimized for a particular olefin
- 5 composition and the hydroformylation catalyst being used in routine preliminary experiments or mathematical process simulations in order to find the conditions which are economically optimal for achieving a very high n/i ratio in the aldehyde product at a very high space-time yield.
- 10 Similar considerations apply to the number of reaction zones in the process of the present invention. Thus, it can be useful, for the purposes of the present invention, to arrange up to 10 reaction zones in series to achieve an economically optimal combination of n/i ratio and space-time yield. Owing to the resulting higher capital costs and/or cost of instrumentation and possibly higher operating costs, this can neutralize
- 15 the economic advantage gained by the improvement in the n/i ratio and the space-time yield. For this reason, the process of the present invention is advantageously carried out in generally from 2 to 8, preferably from 2 to 4 and particularly preferably 2, reaction zones connected in series, with the economically optimal number of reaction zones advantageously being determined in the individual case as a function of the type and
- 20 composition of the olefin composition to be hydroformylated and the hydroformylation catalyst used by means of routine experiments or mathematical process simulations.

It is possible for the hydroformylation product mixture from one reaction zone to be depressurized before entry into the subsequent reaction zone, the aldehydes formed to

25 be separated off and the unreacted olefins be fed into the next reaction zone to be hydroformylated. According to the present invention, preference is given to carrying out no such work-up of the hydroformylation product mixture from one reaction zone before it enters the next reaction zone and depressurizing the hydroformylation product mixture from one reaction zone directly into the next reaction zone. This advantageous

30 embodiment of the process of the present invention is made possible by the total pressure in the downstream reaction zone being lower than in the preceding reaction zone.

The total pressure in the individual reaction zones is generally set as a function of the

35 amount of freshly introduced synthesis gas by regulating the offgas stream from the individual reaction zones, which is generally composed essentially of unreacted synthesis gas, inert gases and hydrocarbons. To set the desired CO/H₂ molar ratio in the individual reaction zones if the CO/H₂ mixture is not introduced with the desired, preset CO/H₂ molar ratio into the individual reaction zones, it can be advantageous to

40 use synthesis gas having a conventional CO/H₂ molar ratio of about 1:1 and to set the

desired CO/H₂ molar ratio in the individual reaction zones by metering in additional amounts of CO or H₂. Here, there is an economically advantageous opportunity of integrating the process of the present invention with other processes by using essentially CO- or H₂-containing offgases from other processes to adjust the CO/H₂ molar ratio. Thus, for example, the CO-containing offgas from methyl formate production can be used to increase the CO/H₂ molar ratio or the H₂-containing offgas from the hydrogenation of aldehydes or enals produced therefrom, e.g. 2-ethylhexenal or 2-propylheptenal, to the corresponding saturated alcohols can be used as H₂ source for reducing the CO/H₂ molar ratio in individual reaction zones. The CO partial pressure can also be reduced by lowering the CO/H₂ pressure in a downstream reaction zone.

The process of the present invention is suitable for the hydroformylation of olefin compositions comprising preferably aliphatic C₄-C₂₀-olefins which have internal and terminal double bonds and may be linear or branched. Examples of such olefin compositions are 1-butene/2-butene mixtures as are obtained industrially as, for example, raffinate II. The term raffinate II refers to the C₄-olefin fraction obtained after butadienes and acetylenes and subsequently isobutene have been separated off from the C₄ fraction from steam crackers. This generally has the following composition:

from 0.5 to 5% by weight of isobutane,
from 5 to 20% by weight of n-butane,
from 20 to 40% by weight of trans-2-butene,
from 10 to 20% by weight of cis-2-butene,
from 25 to 55% by weight of 1-butene,
from 0.5 to 5% by weight of isobutene

and also trace gases such as 1,3-butadiene, propadiene, propene, cyclopropane, methylcyclopropane and vinylacetylene.

Other suitable olefin compositions are, for example, pentene mixtures as are formed, for example, in the acid-catalyzed codimerization of ethene and propene, hexene mixtures from the acid- or nickel-catalyzed (Dimersol process) dimerization of propene or from metathesis processes as described, for example, in EP-A 1 069 101 and EP-A 1 134 271, heptene mixtures, e.g. from the acid- or nickel-catalyzed codimerization of propene and butene, octene mixtures from the dimerization of butenes, for example as described in US-A 5 849 972, nonene mixtures, e.g. from the acid-catalyzed trimerization of propene, decene mixtures, e.g. from the acid-catalyzed dimerization of pentenes, undecene mixtures, e.g. from the codimerization of pentenes and hexenes, dodecene mixtures, e.g. from the acid-catalyzed tetramerization of

propene, the trimerization of butene mixtures, e.g. as described in US-A 5 849 972, and/or the dimerization of hexene mixtures, e.g. as described in WO 00/53546, hexadecene mixtures, e.g. from the tetramerization of butene mixtures, e.g. as described in US-A 5 849 972, octadecene mixtures, e.g. from the dimerization of 5 nonene mixtures, and/or eicosene mixtures from the dimerization of decene mixtures or the tetramerization of pentene mixtures. It goes without saying that it is also possible to use compositions comprising olefins having different numbers of carbon atoms in the process of the present invention. Such olefin compositions having different numbers of carbon atoms can be obtained, for example, by metathesis of butenes as described in 10 EP-A 1 134 271 and EP-A 1 069 101 or via the SHOP process or the Fischer-Tropsch process. A compendium of various suitable processes for preparing compositions comprising higher olefins may be found, for example, in Weissermel, Arpe: Industrielle Organische Chemie, pages 82-99, 5th edition, Wiley-VCH, Weinheim 1998. The 15 aldehydes which can be obtained according to the present invention from these olefin compositions are suitable, for example, as starting materials for preparing plasticizer and surfactant alcohols which can be obtained therefrom either directly by, for example, hydrogenation of the aldehyde to the alcohol or via the steps of aldolization and hydrogenation, for example 2-propylheptanol which can be produced by aldolization of valeraldehyde (obtained by hydroformylation of raffinate II) and 20 subsequent hydrogenation of the aldolization product 2-propylheptenal.

Merely by way of example for the purposes of illustration without any intention of giving an exhaustive list, some representative olefinic compounds which can occur in such olefin compositions are listed below:

25 butenes such as 1-butene, 2-butene and isobutene, pentenes such as 1-pentene, 2-pentene, 2-methyl-1-butene and 2-methyl-2-butene, hexenes such as 1-hexene, 2-hexene, 3-hexene, 2-methyl-1-pentene, 2-methyl-2-pentene, 3-methyl-2-pentene and the 30 various isomers of methylhexene, octenes such as 1-octene, 2-octene, 3-octene, 4-octene and also branched octenes having an internal or terminal double bond, nonenes such as 1-nonene, 2-nonene, 3-nonene, 4-nonene and also branched nonenes having an internal or terminal double bond, decenes such as 1-decene, 2-decene, 3-decene, 4-decene, 5-decene and also branched decenes having an 35 internal or terminal double bond, undecenes such as 1-undecene, 2-undecene, 3-undecene, 4-undecene, 5-undecene and also branched undecenes having an internal or terminal double bond, dodecenes such as 1-dodecene, 2-dodecene, 3-dodecene, 4-dodecene, 5-dodecene, 6-dodecene and also branched dodecenes having an internal or terminal double bond. Tetradecenes, pentadecenes,

hexadecenes, heptadecenes, octadecenes, nonadecenes and eicosenes are likewise suitable.

- The olefin compositions which can be used in the process of the present invention can
5 also comprise diolefins, for example α - ω -diolefins such as 1,3-butadiene, 1,4-penta-
diene, 1,5-hexadiene, 1,6-heptadiene, 1,7-octadiene, 1,8-nonadiene or 1,9-decadiene,
and also diolefins having both internal and terminal double bonds, e.g. 1,3-pentadiene,
1,3-hexadiene, 1,4-hexadiene, 1,3-heptadiene, 1,4-heptadiene, 1,5-heptadiene, 1,3-
octadiene, 1,4-octadiene, 1,5-octadiene, 1,6-octadiene, 1,3-nonadiene, 1,4-nonadiene,
10 1,5-nonadiene, 1,6-nonadiene, 1,7-nonadiene, 1,3-decadiene, 1,4-decadiene,
1,5-decadiene, 1,6-decadiene, 1,7-decadiene, 1,8-decadiene.

- The hydroformylation process of the present invention is carried out using rhodium
catalysts which are dissolved homogeneously in the reaction medium and are
15 complexed with a phosphorous-containing ligand which is capable of isomerizing and
hydroformylating olefins having internal double bonds under the reaction conditions
according to the present invention and has only a relatively small tendency to isomerize
terminal double bonds to internal double bonds under the reaction conditions according
to the present invention. The ligand is advantageously used in an excess over the
20 rhodium, generally at a ligand/Rh molar ratio of from 2 to 300, preferably from 2 to 20
and particularly preferably from 2 to 10.

- The rhodium concentration in the liquid reaction mixture is generally from 10 to
500 ppm by weight, preferably from 30 to 350 ppm by weight and particularly preferably
25 from 50 to 300 ppm by weight. As rhodium source, it is possible to use, for example,
rhodium salts such as rhodium acetate, rhodium chloride or rhodium nitrate, rhodium
complexes such as rhodium acetylacetone and/or rhodium carbonyl compounds such
as $\text{Rh}(\text{CO})_2\text{acac}$, $\text{Rh}_4(\text{CO})_{12}$ or $\text{Rh}_6(\text{CO})_{16}$ (acac: acetylacetone). The type of rhodium
source used is generally not critical to the result of the process of the present invention.
30

- To carry out the hydroformylation, the rhodium compound serving as rhodium source is
generally dissolved or suspended in the reaction mixture, and the ligand to be used is
dealt with similarly. The hydroformylation-active rhodium complex is then formed in situ
in the hydroformylation reactor under the conditions of the hydroformylation reaction,
35 i.e. by reaction of carbon monoxide and hydrogen with the rhodium compound
complexed with the phosphorus-containing ligand. It goes without saying that
preformed rhodium catalyst complexes can also be added to the reaction mixture.

- The process of the present invention is carried out in a homogeneous phase, i.e. the
40 olefin to be hydroformylated, the rhodium hydroformylation catalyst dissolved

homogeneously in the reaction mixture, free ligand and also the aldehyde formed are present in a liquid phase, i.e. the process of the present invention does not provide for hydroformylation in two liquid phases which are present side-by-side.

- 5 The hydroformylation process of the present invention can advantageously be carried out in the presence of solvents. As solvents, preference is given to using the aldehydes which are formed in the hydroformylation of the respective olefins and also their higher-boiling downstream reaction products, i.e. the products of aldol condensation. Solvents which are likewise suitable are aromatics such as toluene and xylenes, hydrocarbons
10 or mixtures of hydrocarbons which can also serve for diluting the abovementioned aldehydes and the downstream products of the aldehydes. Further possible solvents are esters of aliphatic carboxylic acids with alkanols, for example ethyl acetate or Texanol®, ethers such as tert-butyl methyl ether and tetrahydrofuran. In the case of ligands which are sufficiently hydrophilic, it is also possible to use alcohols such as
15 methanol, ethanol, n-propanol, isopropanol, n-butanol, isobutanol, ketones such as acetone and methyl ethyl ketone etc. "Ionic liquids" can also be used as solvents. These are liquid salts, for example N,N'-dialkylimidazolium salts such as N-butyl-N'-methylimidazolium salts, tetraalkylammonium salts such as tetra-n-butylammonium salts, N-alkylpyridinium salts such as n-butylpyridinium salts, tetraalkylphosphonium
20 salts such as tris(hexyl(tetradecyl)phosphonium salts, e.g. the tetrafluoroborates, acetates, tetrachloroaluminates, hexafluorophosphates, chlorides and tosylates.

- The process of the present invention is advantageously carried out using the liquid discharge method. Here, the liquid hydroformylation mixture is continuously taken off
25 from the hydroformylation reactor of a first reaction zone and fed to the hydroformylation reactor of the next reaction zone. Since the downstream reaction zone is operated at a lower total pressure than the preceding zone, the hydroformylation product mixture from the preceding reaction zone can advantageously be depressurized into the hydroformylation reactor of the downstream reaction zone. In
30 general, the hydroformylation product mixture from a first reaction zone is not worked up before it enters the following reaction zone. The downstream reaction zone is operated under the selected reaction conditions which are different from the reaction conditions of the preceding reaction zone. The liquid hydroformylation mixture is generally taken off continuously from the hydroformylation reactor in this downstream
35 reaction zone and is either depressurized into a depressurization vessel in which the pressure is generally from 1 to 35 bar lower, preferably from 3 to 10 bar lower, than the pressure in the hydroformylation reactor to remove gases dissolved therein, e.g. unreacted CO/H₂ mixture, or is, if desired, fed to a further downstream reaction zone, as described. The gases liberated in the pressurization vessel, in particular unreacted
40 CO/H₂ mixture, can, if desired, be recirculated to one of the preceding reaction zones

in order to be reacted further, in which case it can be advantageous to subject this gaseous recycle stream to scrubbing or intermediate condensation in a heat exchanger to remove entrained aldehydes and/or olefins or to discharge a substream of this recycle stream so as to avoid accumulation of inert gases in the reactor. The liquid


5 hydroformylation mixture remaining in the depressurization vessel, which comprises the hydroformylation product, olefins dissolved therein, high boilers, the catalyst and free ligands, can subsequently be passed to a degassing column to recover unreacted olefins. The bottoms from the degassing column, which comprise the hydroformylation product, high boilers, catalyst and free ligands, can subsequently be passed to a

10 distillation column where the hydroformylation product is separated off from the high boilers, the catalyst and free ligand and can be used further, while the high boilers, the catalyst and free ligand are, if desired after concentrating the stream and discharging a substream in order to avoid buildup of high boilers in the reactor, advantageously recirculated to the reactor of one of the preceding reaction zones, preferably the first

15 reaction zone. The aldehyde product can be worked up by various methods of the prior art, for example by the process described in US-A 4,148,830, US-A 6,100,432 or WO 01/58844.

As catalysts which can isomerize double bonds, preference is given, according to the
 20 present invention, to complexes of rhodium with chelating organophosphoramidite or organophosphite or organophosphonite ligands. In these ligands, one or more of the phosphorus atoms can be replaced by arsenic and/or antimony atoms, but preference is given to using phosphorus-containing ligands.

25 Isomerizing hydroformylation catalysts which are suitable for use in the process of the present invention are, for example, rhodium complexes with phosphoramidite ligands of the formula I,




30

where

Q is a bridging group of the formula

18




where

A¹ and A² are each, independently of one another, O, S, SiR^aR^b, NR^c or CR^dR^e, where

5

R^a, R^b and R^c are each, independently of one another, hydrogen, alkyl, cycloalkyl, heterocycloalkyl, aryl or hetaryl,10 R^d and R^e are each, independently of one another, hydrogen, alkyl, cycloalkyl, heterocycloalkyl, aryl or hetaryl or together with the carbon atom to which they are bound form a cycloalkylidene group having from 4 to 12 carbon atoms or the group R^d together with a further group R^d or the group R^e together with a further group R^e forms an intramolecular bridging group D,

15 D is a divalent bridging group selected from among the groups



where

20

R⁹ and R¹⁰ are each, independently of one another, hydrogen, alkyl, cycloalkyl, aryl, halogen, trifluoromethyl, carboxyl, carboxylate or cyano or are joined to one another to form a C₃- to C₄-alkylene bridge,

25

R¹¹, R¹², R¹³ and R¹⁴ are each, independently of one another, hydrogen, alkyl, cycloalkyl, aryl, halogen, trifluoromethyl, COOH, carboxylate, cyano, alkoxy, SO₃H, sulfonate, NE¹E², alkylene-NE¹E²E³⁺X⁻, acyl or nitro,

c is 0 or 1,

30

Y is a chemical bond,

R⁵, R⁶, R⁷ and R⁸ are each, independently of one another, hydrogen, alkyl, cycloalkyl, heterocycloalkyl, aryl, hetaryl, COOR^f, COO⁻M⁺, SO₃R^f, SO₃⁻M⁺, NE¹E²,

$\text{NE}^1\text{E}^2\text{E}^{3+}\text{X}^-$, alkylene- $\text{NE}^1\text{E}^2\text{E}^{3+}\text{X}^-$, OR^f , SR^f , $(\text{CHR}^g\text{CH}_2\text{O})_x\text{R}^f$, $(\text{CH}_2\text{N}(\text{E}^1))_x\text{R}^f$, $(\text{CH}_2\text{CH}_2\text{N}(\text{E}^1))_x\text{R}^f$, halogen, trifluoromethyl, nitro, acyl or cyano,

where

5

R^f , E^1 , E^2 and E^3 are identical or different radicals selected from among hydrogen, alkyl, cycloalkyl and aryl,

10 R^g is hydrogen, methyl or ethyl,

10

M^+ is a cation,

15 X^- is an anion and

15 x is an integer from 1 to 120,

or

20 R^5 and/or R^7 together with two adjacent carbon atoms of the benzene ring to which they are bound form a fused ring system having 1, 2 or 3 further rings,

a and b are each, independently of one another, 0 or 1,

25 P is phosphorus,

25

and

30 R^1 , R^2 , R^3 , R^4 are each, independently of one another, hetaryl, hetaryloxy, alkyl, alkoxy, aryl, aryloxy, cycloalkyl, cycloalkoxy, heterocycloalkyl, heterocycloalkoxy or an NE¹E² group, with the proviso that R¹ and R³ are bound via the nitrogen atom of pyrrole groups bound to the phosphorus atom P or R¹ together with R² and/or R³ together with R⁴ form a divalent group E which contains at least one pyrrole group bound via the pyrrole nitrogen to the phosphorus atom P and has the formula

35

Py-I-W

where

40 Py is a pyrrole group,

I is a chemical bond or O, S, SiR^aR^b, NR^c or CR^hRⁱ,

W is cycloalkyl, cycloalkoxy, aryl, aryloxy, hetaryl or hetaryloxy,

and

5 R^h and R^i are each, independently of one another, hydrogen, alkyl, cycloalkyl, heterocycloalkyl, aryl or hetaryl,


or form a bispyrrole group which is bound via the nitrogen atoms to the phosphorus atom P and has the formula

10

Py-I-Py.

Preferred phosphoramidite ligands are ligands of the formula Ia

15



where

20

R^{15} , R^{16} , R^{17} and R^{18} are each, independently of one another, hydrogen, alkyl, cycloalkyl, heterocycloalkyl, aryl, hetaryl, $W'COOR^k$, $W'COO^-M^+$, $W'(SO_3)R^k$, $W'(SO_3)^-M^+$, $W'PO_3(R^k)(R^l)$, $W'(PO_3)_2(M^+)_2$, $W'NE^4E^5$, $W'(NE^4E^5E^6)^+X^-$, $W'OR^k$, $W'SR^k$, $(CHR^lCH_2O)_yR^k$, $(CH_2NE^4)_yR^k$, $(CH_2CH_2NE^4)_yR^k$, halogen, trifluoromethyl, nitro, acyl or cyano,

25

where

30

W' is a single bond, a heteroatom or a divalent bridging group having from 1 to 20 bridge atoms,

R^k , E^4 , E^5 , E^6 are identical or different radicals selected from among hydrogen, alkyl, cycloalkyl and aryl,

35

R^l is hydrogen, methyl or ethyl,

M^+ is a cation equivalent,

X^- is an anion equivalent and

y is an integer from 1 to 240,

5 where two adjacent radicals R¹⁵, R¹⁶, R¹⁷ and R¹⁸ together with the carbon atoms of the pyrrole ring to which they are bound may also form a fused ring system having 1, 2 or 3 further rings,


10 with the proviso that at least one of the radicals R¹⁵, R¹⁶, R¹⁷ and R¹⁸ is not hydrogen and R¹⁹ and R²⁰ are not linked to one another,

15 R¹⁹ and R²⁰ are each, independently of one another, cycloalkyl, heterocycloalkyl, aryl or hetaryl,

a and b are each, independently of one another, 0 or 1,

15 P is a phosphorus atom,

Q is a bridging group of the formula



20 ,


where

25 A¹ and A² are each, independently of one another, O, S, SiR^aR^b, NR^c or CR^dR^e, where

30 R^a, R^b and R^c are each, independently of one another, hydrogen, alkyl, cycloalkyl, heterocycloalkyl, aryl or hetaryl,

35 R^d and R^e are each, independently of one another, hydrogen, alkyl, cycloalkyl, heterocycloalkyl, aryl or hetaryl or together with the carbon atom to which they are bound form a cycloalkylidene group having from 4 to 12 carbon atoms or the group R^d together with a further group R^d or the group R^e together with a further group R^e forms an intramolecular bridging group D,

D is a divalent bridging group selected from among the groups



where

5 R⁹ and R¹⁰ are each, independently of one another, hydrogen, alkyl, cycloalkyl, aryl, halogen, trifluoromethyl, carboxyl, carboxylate or cyano or are joined to one another to form a C₃- to C₄-alkylene bridge,

10 R¹¹, R¹², R¹³ and R¹⁴ are each, independently of one another, hydrogen, alkyl, cycloalkyl, aryl, halogen, trifluoromethyl, COOH, carboxylate, cyano, alkoxy, SO₃H, sulfonate, NE¹E², alkylene-NE¹E²E³⁺X⁻, acyl or nitro,

c is 0 or 1,

15 R⁵, R⁶, R⁷ and R⁸ are each, independently of one another, hydrogen, alkyl, cycloalkyl, heterocycloalkyl, aryl, hetaryl, COOR^f, COO⁻M⁺, SO₃R^f, SO₃⁻M⁺, NE¹E², NE¹E²E³⁺X⁻, alkylene-NE¹E²E³⁺X⁻, OR^f, SR^f, (CHR^gCH₂O)_xR^f, (CH₂N(E¹))_xR^f, (CH₂CH₂N(E¹))_xR^f, halogen, trifluoromethyl, nitro, acyl or cyano,

20

where

R^f, E¹, E² and E³ are identical or different radicals selected from among hydrogen, alkyl, cycloalkyl and aryl,

25

R^g is hydrogen, methyl or ethyl,

M⁺ is a cation,

30

X⁻ is an anion and

x is an integer from 1 to 120,



or

35



R⁵ and/or R⁷ together with two adjacent carbon atoms of the benzene ring to which they are bound form a fused ring system having 1, 2 or 3 further rings.

Such ligands are subject matter of WO 02/083695, which is hereby fully incorporated by reference and where the preparation of these ligands is also described. Preferred ligands from this class are, for example, the following compounds, with this listing being merely for the purposes of illustration and not implying any restriction in respect of the


5 ligands which can be employed:





10



15





5





10


25




5



10


26

12




13

5




14


10



15




16




17

5




18




19

10


28




5





10





20




29**24****25**

5


**26****27**

10

30




28




29


5




30




31






36

5




37




38

10

33




39




40

5




41

34




42




43

5



44


35




45

5

46





47





10

48







5




37



52




53




54

5




55

38



56



57

5


Et: ethyl

Me: methyl


Suitable phosphoramidite ligands for the isomerizing hydroformylation using rhodium complexes as catalysts also include the phosphoramidite ligands described in WO 98/19985 and WO 99/52632, which have 2,2'-dihydroxy-1,1'-binaphthylene or 2,2'-dihydroxy-1,1'-binaphthylene bridging groups which bear heteroaryl groups such as pyrrolyl or indolyl groups bound to the phosphorus atom via the nitrogen atom, for example the ligands:

15

39




58






59


5




60

40**61****5****62****63**


41




64



5




66




10

42




68





69

5




70


43




5



44




74




75

5




76


45



5





79




- 10 The 1,1'-biphenylene or 1,1'-binaphthylene bridging groups of these ligands can be further bridged via the 1,1 position by a methylene group (CH_2-), a 1,1-ethylene group ($\text{CH}_3-\text{CH}-$) or a 1,1-propylene group ($\text{CH}_3-\text{CH}_2-\text{HC}-$).

- 15 Suitable phosphonite ligands for the isomerizing hydroformylation using rhodium complexes as catalysts are, inter alia, the ligands described in WO 98/19985, for example:



46




5



- 10 Suitable ligands for the isomerizing hydroformylation using rhodium complexes as catalysts also include phosphite and phosphonite ligands as are described, for example, in WO 01/58589. Merely for the purposes of illustration, the following ligands may be mentioned by way of example:




5



- 10 Further well-suited ligands for the isomerizing hydroformylation using rhodium complexes as catalysts are phosphine ligands having the xanthenyl-bisphosphoxanthenyl skeleton, as are described, for example, in WO 02/068371 and


EP-A 982314. Merely for the purposes of illustration, some of these ligands are listed below by way of example:

5




10

87




88




15


89



49






5




10

Further suitable chelating phosphite ligands for the isomerizing hydroformylation using rhodium complexes of these ligands as catalysts are, for example, ligands of the formulae II, III and IV






5




where G is a substituted or unsubstituted divalent organic bridging group having from 2 to 40 carbon atoms, M is a divalent bridging group selected from among $-C(R^w)_2-$, $-O-$, $-S-$, NR^y , $Si(R^t)_2-$ and $-CO-$, where the groups R^w are identical or different and are each hydrogen, an alkyl group having from 1 to 12 carbon atoms or a phenyl, tolyl or anisyl group, the group R^y is hydrogen or a substituted or unsubstituted hydrocarbon group having from 1 to 12 carbon atoms, the groups R^t are identical or different and are each hydrogen or a methyl group, m is 0 or 1, the groups Ar are identical or different and are each an unsubstituted or substituted aryl group, the index k is 0 or 1, the groups R^x are identical or different and are each an unsubstituted or substituted monovalent alkyl or aryl group and R^y is a divalent organic radical selected from among unsubstituted

and substituted alkylene, arylene, arylene-alkylene-arylene and bis-arylene groups. Merely for the purposes of illustration without implying any restriction, mention may be made by way of example of the following chelating phosphite ligands which can be used in the process of the present invention:


5






10




95







53



99




100






101

5





102


54





55





5






5




10

57




113




114

5




115




116

10

58




117



118

5




119


120

10

59




121





122


5




123

60


125





5



126



61




5

Such bisphosphite chelating ligands and other bisphosphite chelating ligands are subject matter of EP-A 213 369 and US-A 4 769 498 and their preparation is described there.


10 In place of the abovementioned bisphosphite chelating ligands, it is also possible to use monodentate monophosphite ligands of the formula V




15 for complexing the rhodium hydroformylation catalyst and as free ligand in the process of the present invention. The suitability of such ligands and their complexes with rhodium as catalysts for isomerizing hydroformylation is known. In the monophosphite ligands of the formula IV, the radicals R^{S} , R^{T} and R^{U} are, independently of one another, identical or different organic groups generally having from 1 to 30, preferably from 5 to 20, carbon atoms, for example substituted or unsubstituted alkyl, aryl, arylalkyl, cycloalkyl and/or heteroaryl groups. Owing to their increased hydrolysis and degradation stability, particular preference is given to sterically hindered monophosphite ligands as are described, for example, in EP-A 155 508. Merely for the purposes of illustration, the following monophosphite ligand structures may be 25 mentioned by way of example:




5




10



63




133



134



5

Known ligands for the isomerizing hydroformylation using rhodium complexes as catalysts also include bidentate ligands which have a phosphinite or phosphine group in addition to the phosphite group in the ligand molecule. Such ligands are described, inter alia, in WO 99/50214. Merely for the purposes of illustration, some examples of such ligands are shown below:




135


64




5




65



139




140




141

5

66




142





143

5




144


67




5



68




148




149

5




150

69




151




152

5



153



Bu^t: tertiary butyl

Ph: phenyl

5

The ligand types described above can be used in the form of their complexes with rhodium and/or as free ligands in the process of the present invention. Preference is given to using rhodium complexes with phosphoramidite ligands having a xanthene backbone, as are described in WO 02/083695, as catalysts for the isomerizing

10 hydroformylation in the process of the present invention.

The process of the present invention makes it possible to hydroformylate olefin compositions comprising both α -olefins and olefins having internal double bonds to give the corresponding aldehydes in an n/i ratio higher than that corresponding to the
15 proportion of α -olefins in the olefin composition and at a higher space-time yield than is obtainable in conventional processes without the cascading into two or more reaction zones according to the present invention.


The process of the present invention is illustrated below with the aid of examples.

20

Examples

Synthesis of ligand 53:

5



53

28.5 g (218 mmol) of 3-methylindole (skatole) together with about 50 ml of dried toluene were placed in a reaction vessel and the solvent was distilled off under reduced pressure to remove traces of water by azeotropic distillation. This procedure was repeated once more. The residue was subsequently taken up in 700 ml of dried toluene under argon and the mixture was cooled to -65°C. 14.9 g (109 mmol) of PCl_3 followed by 40 g (396 mmol) of triethylamine were then added slowly at -65°C. The reaction mixture was brought to room temperature over a period of 16 hours and then refluxed for 16 hours. 19.3 g (58 mmol) of 4,5-dihydroxy-2,7-di-tert-butyl-9,9-dimethylxanthene in 300 ml of dried toluene were added to the reaction mixture, and the mixture was then refluxed for 16 hours and, after cooling to room temperature, the precipitated colorless solid (triethylamine hydrochloride) was filtered off with suction, the solvent was distilled off and the residue was recrystallized twice from hot ethanol. Drying under reduced pressure gave 36.3 g (71% of theory) of a colorless solid. ${}^{31}\text{P}$ -NMR (298K): $\delta = 105$.

Example 1

Hydroformylation of 1-butene, CO:H₂ molar ratio = 1:1

25 5.5 mg of $\text{Rh}(\text{CO})_2\text{acac}$ (acac=acetylacetone) and 200 mg of ligand 53 were weighed out separately, each dissolved in 5 g of toluene, mixed and treated with 10 bar of synthesis gas (CO:H₂ = 1:1) at 90°C (preactivation). After 1 hour, the mixture was depressurized. 9.9 g of 1-butene were then added via a pressure lock, a total pressure of 17 bar was set by means of synthesis gas (CO:H₂ = 1:1) and hydroformylation was carried out at 90°C for 2 hours (109 ppm of Rh; ligand 53:Rh molar ratio $\approx 10:1$). After the reaction time indicated, the autoclave was cooled, carefully vented via a cold trap and the collected reaction product mixtures (reactor and cold trap) were analyzed by means of gas chromatography. The conversion was 99%, the yield of valeraldehyde

was 92% and the linearity (proportion of n product) was 98.5%. The yield of 2-butene (isomerization product) was 7%.

The CO and H₂ partial pressures at the beginning of the reaction were each 6 bar.

5

The linearity (proportion of n product) is defined as the amount of n-valeraldehyde divided by the sum of n-valeraldehyde and i-valeraldehyde multiplied by 100.

Example 2

10 Hydroformylation of 1-butene, CO:H₂ molar ratio = 1:2

5.4 mg of Rh(CO)₂acac (acac=acetylacetone) and 200 mg of ligand 53 were weighed out separately, each dissolved in 5 g of toluene, mixed and treated with 10 bar of synthesis gas (CO:H₂ = 1:2) at 90°C (preactivation). After 1 hour, the mixture was 15 depressurized. 10.1 g of 1-butene were then added via a pressure lock, and a total pressure of 17 bar was set by means of synthesis gas (CO:H₂ = 1:2). The gas feed was then changed over to synthesis gas (CO:H₂ = 1:1) to ensure a constant CO:H₂ molar ratio of 1:2 in the reactor. Hydroformylation was subsequently carried out at 90°C for 20 2 hours (105 ppm of Rh; ligand 53:Rh molar ratio ≈10:1). The conversion was 98%, the yield of valeraldehyde was 49% and the linearity (proportion of n product) was 95.8%. The yield of 2-butene (isomerization product) was 46%.

The CO partial pressure at the beginning of the reaction was 4 bar, and the H₂ partial pressure at the beginning of the reaction was 8 bar.

25

Example 3

Hydroformylation of 2-butene, CO:H₂ molar ratio = 1:1

5.0 mg of Rh(CO)₂acac (acac=acetylacetone) and 176 mg of ligand 53 were weighed 30 out separately, each dissolved in 5 g of toluene, mixed and treated with 10 bar of synthesis gas (CO:H₂ = 1:1) at 90°C (preactivation). After 1 hour, the mixture was depressurized. 11.3 g of 2-butene were then added via a pressure lock, and a total pressure of 17 bar was set by means of synthesis gas (CO:H₂ = 1:1). Hydroformylation was subsequently carried out at 90°C for 4 hours (93 ppm of Rh; ligand 53:Rh molar 35 ratio ≈10:1). The conversion was 12%, the yield of valeraldehyde was 10% and the linearity (proportion of n product) was 88.5%.

The CO and H₂ partial pressures at the beginning of the reaction were each 6 bar.

Example 4

Hydroformylation of 2-butene, CO:H₂ molar ratio = 1:2

5.0 mg of Rh(CO)₂acac (acac=acetylacetone) and 176 mg of ligand 53 were weighed
5 out separately, each dissolved in 5 g of toluene, mixed and treated with 10 bar of
synthesis gas (CO:H₂ = 1:2) at 90°C (preactivation). After 1 hour, the mixture was
depressurized. 11.2 g of 2-butene were then added via a pressure lock, and a total
pressure of 17 bar was set by means of synthesis gas (CO:H₂ = 1:2). The gas feed was
then changed over to synthesis gas (CO:H₂ = 1:1) to ensure a constant CO:H₂ molar
10 ratio of 1:2 in the reactor. Hydroformylation was subsequently carried out at 90°C for
4 hours (93 ppm of Rh; ligand 53:Rh molar ratio ≈10:1). The conversion was 34%, the
yield of valeraldehyde was 32% and the linearity (proportion of n product) was 93%.

15 The CO partial pressure at the beginning of the reaction was 4 bar, and the H₂ partial
pressure at the beginning of the reaction was 8 bar.

Example 5

Hydroformylation of 2-butene, CO:H₂ molar ratio = 1:9

20 5.0 mg of Rh(CO)₂acac (acac=acetylacetone) and 176 mg of ligand 53 were weighed
out separately, each dissolved in 5 g of toluene, mixed and treated with 10 bar of
synthesis gas (CO:H₂ = 1:9) at 90°C (preactivation). After 1 hour, the mixture was
depressurized. 11.2 g of 2-butene were then added via a pressure lock, and a total
pressure of 17 bar was set by means of synthesis gas (CO:H₂ = 1:9). The gas feed was
25 then changed over to synthesis gas (CO:H₂ = 1:1) to ensure a constant CO:H₂ molar
ratio of 1:9 in the reactor. Hydroformylation was subsequently carried out at 90°C for
4 hours (93 ppm of Rh; ligand 53:Rh molar ratio ≈10:1). The conversion was 64%, the
yield of valeraldehyde was 46% and the linearity (proportion of n product) was 96%.

30 The CO partial pressure at the beginning of the reaction was 1.2 bar, and the H₂ partial
pressure at the beginning of the reaction was 10.8 bar.

Example 6

Hydroformylation of trans-2-butene, CO:H₂ = 1:1

35 5.0 mg of Rh(CO)₂acac (acac= acetylacetone) and 187 mg of ligand 53 were
weighed out separately, each dissolved in 5 g of toluene, mixed and treated with 10 bar
of synthesis gas (CO:H₂ = 1:1) at 90°C (preactivation). After 1 hour, the mixture was
depressurized. 10.4 g of trans-2-butene were then added via a pressure lock and a
40 total pressure of 12 bar was set by means of synthesis gas (CO:H₂ = 1:1).

Hydroformylation was subsequently carried out at 90°C for 4 hours (97 ppm of Rh; ligand 53:Rh = 10:1). The conversion was 33%, the yield of valeraldehyde was 30% and the linearity (proportion of n product) was 95%.

- 5 The CO and H₂ partial pressures at the beginning of the reaction were each 3.5 bar.

Example 7

Continuous hydroformylation of raffinate II using Rh/ligand 53

- 10 In a continuously operated apparatus as shown in the drawing, comprising two stirring autoclaves (1 and 2) which each had a liquid capacity of 1 l and were connected in series, a pressure separator (3), a depressurized and heated container for separating off C4-hydrocarbons (4) and a wiped film evaporator (5) for separating the catalyst-containing high boiler phase from the product phase, raffinate II (29% by weight of 1-butene, 52% by weight of 2-butene, 19% by weight of butanes and other C4-hydrocarbons) was hydroformylated using rhodium and ligand 53 as catalyst. The catalyst return stream from the distillation (5) to the reactors was about 130 g/h, and the raffinate feed rate was about 70 g/h. The rhodium concentration in the reactors was about 100 ppm at a ligand/metal molar ratio of ≈10:1 (mol:mol), and the temperature of the first reactor was 70°C and that of the second reactor was 90°C. The first reactor was supplied with synthesis gas having a CO:H₂ molar ratio of 1:1 and was operated at a total pressure of about 22 bar. Additional introduction of H₂ into the second reactor, which was operated at about 20 bar, enabled the CO content of the synthesis gas to be regulated via the offgas concentration to any value in the range from about 50% of CO to about 1% of CO. In steady-state operation at a CO:H₂ molar ratio of 1:25 in the second reactor (first reactor: CO:H₂ molar ratio = 1:1) over a representative period of 13 days, an aldehyde yield of 49% and a proportion of n product of 96.1% were achieved.